

Introduction to CTF3

G.Geschonke
CERN / PS

Aim of review:

Review the technical solutions
are they realistic ?

Give us technical advice
Comment on alternatives

Guide our funding bodies:
CERN
Collaborations

CTF3 is only possible as International collaboration

INFN Frascati

LAL Orsay

Rutherford Appleton Laboratory

SLAC

Strathclyde University

Uppsala University

CTF3 is not a user facility

Experimental machine :

Demonstration of the RF power generation scheme for CLIC

- Novel drive beam scheme in the two-beam scenario
- This two-beam scheme is not limited to CLIC

long RF pulse at low frequency

==> short RF pulse at high frequency with high power
using an electron beam for energy storage

high efficiency

Demonstration of major CLIC Components

RF power source at 30 GHz with nominal CLIC parameters

Make use of already existing material:

LPI complex available since LEP shut-down:

LEP injector Linac **LIL** and Electron-Positron Accumulator **EPA**


Building : Linac tunnel, space for rings, control room

Hardware:

3 GHz RF system: klystrons, modulators, accelerating sections
magnets, power supplies,
control system



==> some technical choices are a consequence of existing equipment

CLIC - CTF3






| | | CTF3 | CLIC (3 TeV) |
|--|---------|----------|--------------|
| Drive beam | | | |
| Acceleration frequency | MHz | 2 998.55 | 937 |
| repetition rate | Hz | 5 | 100 |
| energy | MeV | 150 | 1180 |
| Number of accelerating structures | | 16 + 2 | 182 |
| average current after linac | A | 3.5 | 7.5 |
| Number of klystrons | | 10 | 182 x 2 |
| Number of RF pulse compressors | | 9 | 0 |
| Beam pulse length | μ s | 1.4 | 92 |
| Bunch spacing before compression | cm | 20 | 64 |
| Delay Loop length | m | 42 | 39 |
| Combiner Ring length | m | 84 | 78 |
| Average beam current after compression | A | 35 | 240 |
| Bunch spacing after compression | cm | 2 | 2 |
| Drive beam energy per pulse | kJ | 0.8 | 814 |
| average beam power | kW | 4.1 | 81 000 |
| Main beam | | | |
| Number of accelerating structures | | max 8 | 22 x 976 |
| RF Pulse length | ns | 140 | 130 |
| Acceleration Frequency | GHz | 30 | 30 |
| Acceleration Gradient | MV/m | 150 | 150 |

“Phase-coding” of bunches




Bunch frequency multiplication - Combiner Ring injection




Generic layout of CTF3

CTF3 - Test of Drive Beam Generation, Acceleration & RF Multiplication by a factor 10



CTF3 layout - Nominal phase



A possible housing of the CLIC Test Facility (CTF3) in the LEP Pre-injector building

Main objectives and challenges

Drive beam production:

3.5 A,
Estimation: Stability of Voltage
and beam current of 10^{-3} !
satellite bunches
bunch phase coding

Thermionic injector
wide bw 1.5 GHz klystron

Alternative: Laser gun

Drive beam accelerator:

Near 100% beam loading
high beam current in short bunches
beam stability

strong damping of HOM ,
new RF structures

Delay loop, Combiner ring, bunch compressor

injection with RF deflector
isochronous lattice
Impedance
coherent synchrotron radiation
handling of 35 A beam current


bunch length manipulation

3 GHz RF:

pulse compression, long flat-top

longer RF pulse, phase ramping
New BOC development

Drive beam accelerating structure





High beam current =>




Beam induced modes have to be damped

← Prototype of TDS structure built, RF power tested


New structure type has been developed :

(SICA = Slotted Iris Constant Aperture)






| | | |
|----------------------|----------|---------------|
| Bunch Length (rms) | 0.5-2.5 | mm |
| Bunch Charge | 0.1-2.4 | nC |
| Norm Emittance (rms) | 100 | π mm mrad |
| β -functions | 0.5-15 | m |
| Beam size | 0.25-1.5 | mm |



2005 - 2006

RF power plant 3 GHz and 1.5 GHz



Major building modifications

Radiation shielding

Beam power 5 kW !

shielding assumes :
permanent beam loss of only 5% (250 W)
beam loss monitors in interlock chain shut-off beam



additional shielding required:

some outside walls

between accelerator tunnel and klystron gallery above
up to 20 cm of iron

above EPA:
additional 90 cm concrete


Other building modifications:

make room for DL
new CLEX building


Construction in phases

Preliminary phase
2001 / 2002

LPI + modified EPA
new e-gun
only 8 accelerating sections
EPA ring 17 mm shorter
transfer lines and EPA isochronous




LPI in 2001-2002



demonstrate bunch recombination by factor 3-5
using 2 RF deflectors

limited beam current


Initial phase
2003 / 2004



new injector (no Sub-harmonic bunchers ...)
new accelerating structures for DBA
30 GHz test station after linac

transfer lines
combiner ring

combination tests can be done at reduced bunch charge



DBA = Drive Beam Accelerator
 CR = Combiner Ring
 DL = Delay Loop
 SHB = Sub Harmonic Buncher
 CLEX = CTR Experimental area (30GHz)

From LPI to CTF3

REVISED
 13-28-2001

Collaborations

LAL:

gun, HV deck

pre-bunchers

CLIO-type gun for prel. phases already delivered

SLAC:

triode assembly

Injector optics and layout

INFN Frascati:

transfer lines, bunch lengthening chicane


Delay Loop layout and hardware

Combiner Ring layout and hardware

RF deflectors

Fast kickers

Participate in commissioning and exploitation



RAL and Strathclyde University:

Laser for Photo-Injector option

Uppsala University:

mm wave detector for beam diagnostics

participation in commissioning