



# **CTF3 Preliminary phase**

## Experiments done in LPI and planned in CTF3

L. Rinolfi

L.R. 3 October 2001





The CLIC Test Facility (CTF3) has been proposed to demonstrate the technical feasibility of the key concepts of the CLIC RF power source:

- 1) generation of a high-current, high-frequency drive-beam by combination of electron bunch trains in an isochronous ring using transverse RF deflectors.
- 2) operation with a fully-loaded drive-beam accelerator.
- 3) CTF3 will also provide the 30 GHz RF power needed to test the CLIC accelerating structures and components at the nominal gradient and pulse length (150 MV/m for 130 ns).

These issues will be fully covered in the CTF3 Nominal phase (2004-2005)

- The Preliminary Phase of CTF3 (2001-2002) is a demonstration of the first point, but at low-charge and short pulse.
  - \* Also acquire experience in combiner ring operation and develop tools for next phases.

This demonstration is possible using the existing hardware - However, it needs a large number of modifications of the former LPI (LEP Pre-Injector) complex.

#### **CERN** - European Laboratory for Particle Physics



CLIC Note 470

#### Beam dynamics for the CTF3 preliminary phase

R. Corsini, A. Ferrari, L. Rinolfi, T. Risselada, P. Royer, F. Tecker

#### Abstract

In the framework of the CLIC RF power source studies, the new scheme of electron pulse compression and bunch frequency multiplication, using injection by RF deflectors into an isochronous ring, will be tested at CERN during the CTF3 preliminary phase. The present LPI complex will be modified in order to allow a test of this scheme at low charge. The design of the new front-end, of the modified linac, of the matched transfer line, and of the isochronous ring lattice is presented here. The results of the related beam dynamics studies are also discussed.

Geneva, Switzerland January 30, 2001





#### The LPI until April 2001





#### General description of CTF3 preliminary phase streak camera **RF** deflectors measurement gun & bunching system injection line Linac (8 structures) 350 MeV 4 MeV isochronous ring matching section None Carlore ejection line Beam structure 2 House in linac Beam structure after combination (factor 5) **Bunch** spacing **Bunch** spacing 420 ns 6.6 ns 10 cm 2 cm Pulse Length 6.6 ns total Length 2.53 µs - Peak Beam Current 0.5 A Beam Peak Current 2.5 A

CTF3 Review Committee





$$\eta = \frac{1}{\gamma^2} - \alpha$$
  
where  $\gamma = \text{Relativistic factor E/E}_0$   $\alpha = \text{Momentum compaction}$ 

For leptons storage rings:

 $\gamma$  is very large, then  $\eta \sim |\alpha|$ 

Momentum compaction

$$\alpha = \frac{1}{C} \int_{0}^{C} \frac{D(s)}{\rho} ds$$

Modification of dispersion using N quadrupoles [1]

$$C\Delta\alpha = -\sum_{i=1}^{N} \Delta K_i L_i D_i D_i^*$$

C = Ring circumference  $\Delta K = normalised$  gradient increment L = quadrupole length D = unperturbed dispersion at quadrupole  $D^* = modified$  dispersion at quadrupole

Small gradient change:

$$C\Delta\alpha \approx -\sum_{i=1}^{N} \Delta K_i L_i D_i^2$$

[1] T. Risselada, "Proceedings of the Fifth General Accelerator Physics Course", CERN 94-01, 1994.





#### Momentum compaction

$$\alpha = \frac{\frac{dC}{C}}{\frac{dp}{p}}$$

Time variation

$$d\mathbf{C} = \mathbf{c} \, d\mathbf{t} = \boldsymbol{\alpha} \mathbf{C} \; \frac{d\mathbf{p}}{\mathbf{p}}$$

After N turns

$$N dt = \alpha \frac{C}{c} \frac{dp}{p} N$$

Bunch to bunch distance

 $\Delta t(N) = \Delta t(0) + N dt$ 

#### Bunch to bunch distance versus $\alpha$

$$\Delta t(N) = \Delta t(0) + \alpha \frac{C}{c} \frac{dp}{p} N$$







Layout for the micro-bunch measurements. A streak camera uses the synchrotron light coming from the EPA ring.

Two screens allow measurements in a dispersive region (MSR56) and in a non-dispersive region (MSR52).





#### Pulse profiles in time



Streak camera image of the electron pulse (April 1999)

Streak camera image of the total pulse and corresponding time profile

#### Nominal EPA optics



#### I sochronous EPA optics





## Measurements with streak camera in EPA ring - 2





Streak camera images and time profiles for different settings of the QFL quadrupole family, around a = 0 (20 turns)

nominal optics ( $\mathbf{a} = 3.4 \times 10^{-2}$ ) isochronous optics ( $\mathbf{a} = 2.3 \times 10^{-4}$ )



Bunch-to-bunch spacing as a function of the number of turns for the normal (squares) and the isochronous optics (circles).



CTF3 & CLIC requirement  $|\mathbf{a}| \le \pm 1 \times 10^{-4}$ 

Comparison between the momentum compaction evaluated with MAD (solid line) and the estimation based on the measured bunch distance (circles) as a function of QFL current variation







For a given bunch length, the energy spread depends on the phase of the bunch with respect to the rf wave in the linac.

The contribution of beamloading to the energy spread is made negligible by reducing the pulse charge.







The phase between the bunch and the rf wave is changed and the energy spread is recorded using a SEM-grid at 2 different energies in the linac (LIL).

From the energy spread, the bunch length is deduced in the linac.





- In order to cover combination factors from 3 to 5, a frequency variation of  $\pm$  150 kHz is needed
- The frequency change must be followed by a corresponding change of  $\pm$  3° C in the operating temperature of the bunching system, the accelerating structures and the RF deflectors
- The behavior of the bunching system and of the accelerating structures has been tested experimentally in December 2000



- No temperature compensation
  - The bunching system OK for a frequency range of -50 / +100 kHz
  - The accelerating gradient is reduced, as expected
- Temperature compensation
  - No measurable effect on beam performance (bunch length, beam energy and momentum spread) over the full frequency range



Beam energy at the end of the Linac versus RF frequency change



### Power Tests of the RF deflectors





mrad 
$$f \approx 585 \frac{\sqrt{P}}{E}$$
 MW

Nominal deflection angle f = 4.5 mrad Nominal beam energy E = 350 MeV Nominal input power P = 7 MW





Forward power signal (2.5 ms, 7 MW, 3 GHz)





**The linac:** Twiss parameters and emittances, Energy gains in the RF structures, Trajectory measurements, ....

*The ring:* Circumference measurements, Synchrotron frequency, ...

## **Experimental** program for 2001 and 2002

Tests of injection with RF deflectors in the isochronous ring (single pulse)

Demonstration of bunch train combination for combination factors 3, 4, 5

Possible further tests:

Bunch length and phase HF monitor (Uppsala University)

Test of new deflector prototypes (INFN-Frascati)

RF deflector stability studies

Coherent Synchrotron Radiations studies,

CTF3 Review Committee

. . . . . . .





Friday 21<sup>st</sup> September 2001



R. Corsini, B. Dupuy, L. Rinolfi, P. Royer, F. Tecker





- Collaboration with other Institutes
  - LAL (CLI O gun)
  - Frascati (RF deflectors)
  - Uppsala University (Optics design)
  - IPN Orsay (RF wave guides installation)
- Technical Installation Committee (TIC)
  - All groups of the PS Division
  - EST, LHC, ST, TIS Divisions
- People participating in the 2001 commissioning with beam
  - CERN: 5 accelerator physicists
  - Uppsala University: 1 accelerator physicist (part-time)
  - Frascati: 3 accelerator physicists per week with beam (part-time)
  - Possible other contributions from CERN and external Institutes (under discussions)