





Concept d'Accélérateur Linéaire pour Faisceau d'Electrons Sonde

CALIFES



Probe Beam Linac
DAPNIA / IN2P3 / CERN collaboration

rf-gun



Probe Beam Linac Parameters

- GOAL : to mimic the main beam in order to measure precisely the performances of the CLIC 30 GHz structures
- Installation in 2007 and Commissioning in 2008



Parameters		Motivation
Energy	~ 200 MeV	Avoid beam disruption in high RF fields
norm. rms Emittance	$< 20 \pi$ mm mrad	Fit in 30 GHz structure acceptance
Energy spread	$< \pm 2\%$	Measurement resolution
Bunch charge	0.5 nC	~ CLIC parameters
Bunch spacing	0.333 ns	
Number of bunches	1 – 64	Measure 30 GHz structure transients
rms bunchlength	< 0.75 ps	Acceleration with 30 GHz

multibunch operation : high beam current

$$Q_b = 0.5 \text{ nC and } F_b = 3 \text{ GHz} \Rightarrow I_0 = 1.5 \text{ A}$$



generation of bunches :

- **RF photo gun**

better emittance and more flexibility in time structure

acceleration :

- **re-use of LIL sections** but high beam-loading

$\Delta E/E \sim 10\%$ after 20 ns (64 bunches) for 1.5 A

bunch compression :


- **magnetic chicane** : doesn't work for multibunch mode

the required R_{56} correlation term for single bunch rotation will introduce a large phase-shift between 1st and last bunch

(ex. $R_{56} = 0.05 \text{ m} \Rightarrow \Delta\varphi = 180^\circ$!!! at 30 GHz)

- **velocity bunching** : 3 LIL sections are required


1 for compression and 2 for acceleration




$$\Delta\phi_{\infty} = \frac{\sin\phi_0}{\sin\phi_{\infty}} \Delta\phi_0 + \frac{1}{2\alpha\gamma_0^2 \sin\phi_{\infty}} \Delta\gamma_0 + \frac{1}{2} \left[\frac{\cos\phi_0}{\sin\phi_{\infty}} - \frac{\cos\phi_{\infty} \sin^2\phi_0}{\sin^3\phi_{\infty}} \right] (\Delta\phi_0)^2$$

bunchlength after compression dominated by




- initial energy spread and
- space charge




Velocity bunching (single bunch results)



LAL





σ_x (m)





Velocity bunching (single bunch results)





Effect of beam-loading


LIL section = quasi-constant gradient structure


9 constant impedance families linked by 4 linearly tapered transition cells

⇒ Transient calculations for field set up and beam loading

Analysis using the coupled-resonator model


- any accelerating structure (CI, CG, quasi-constant, etc)
- space harmonics included
- dispersive effects included (section = passband filter)
- any waveform of input *rf* pulse
- beam interaction : propagation of the induced waves with dispersive effects





Beam-loading « on crest » acceleration

64 bunches $Q_b=0.5$ nC $F_b=3$ GHz $\Rightarrow 1.5$ A




Phase and energy deviation :

$$\Delta E = 8.87 \text{ MeV}$$

$$\Delta\phi = 0.2^\circ @ 3\text{GHz}$$




$$\Rightarrow 2^\circ @ 30\text{GHz}$$

For the whole linac $\Rightarrow \delta p/p \sim 11\% !!$




compression LIL section

compression : « off-crest » beam-loading
⇒ energy drop + large phase shift



Energy and Phase deviations :




$$\Delta E = 2.8 \text{ MeV} \quad \Delta\phi = 6.8^\circ @3\text{GHz} \Rightarrow 68^\circ @30\text{GHz}$$



1st compensation method


section detuning to compensate the phase shift $\Delta F = + 0.789$ MHz
extra cooling required $\sim 15^\circ$

$$\Delta\phi_b = \Delta\omega T = 6^\circ \text{ between 1st and last bunch}$$



Energy and Phase deviations :

$$\Delta E = 1.5 \text{ MeV} \quad \Delta\phi = 0.07^\circ @ 3\text{GHz} \Rightarrow 0.7^\circ @ 30\text{GHz}$$



2nd compensation method

magnetic chicane to compensate the multi-bunch phase-shift without altering the single-bunch characteristics

$$\Delta\phi = R_{56} \frac{\Delta E}{E} \frac{2\pi}{\lambda}$$

for 0.5 nC

~6°

10%



⇒ R₅₆ = 0.017 m


for 0.25 nC

⇒ R₅₆ = 0.014 m

The compact CTF2 chicane (length ~ 2m) with R₅₆ from 6 to 90 mm is a good candidate to perform this compensation


single-bunch : slight increase of the bunchlength can be canceled by a small correlation term ~ 1.5° RF phase shift






Initial linac scheme

RF photo gun with 0.5 nC bunch charge (Q.E. ~ 1%)
1 compression LIL section + 2 acceleration LIL sections
2 RF sources







while keeping the main objective


main changes :


- in-situ photocathode prep chamber \Rightarrow Q.E. degraded $\Rightarrow Q_b \sim 0.25$ nC
- 1 single RF source






reference scheme






40
m

Collab. meeting 2004



3 LIL sections + « multibunch » chicane



total length ~24 m from left wall

⇒ 2-branch dipole, Instrumentation Test Beam ~10 m




Alternative scheme to save space

Theoretically & experimentally, it has been shown that for low charge <1 nC **bunch compression can take place in a photocathode rf gun**

when rf gun phase $\rightarrow -90^\circ$ (zero crossing)


"Experimental observation of high-brighness microbunching in a photocathode rf e gun" X.J. Wang, X. Qiu, I. Ben-Zvi PRE, vol.54 (oct. 1996)





ϵ_x ($\mu\text{m}\cdot\text{rad}$)

transverse emittance is OK



Conclusion :

to further decrease the bunchlength down to 225 μm at 0.5 nC


\Rightarrow increase field (85 \rightarrow 120 MV/m)

\Rightarrow and/or go closer to zero-crossing but transmission < 100%


the rf gun compression option can save


1 LIL section and magnetic chicane \sim 7 m

it is worth checking carefully ...




Diagnostics Beam Line





Bunch length measurement


Ele: 11 [2.6475 m] NGOOD : 30000 / 30000 TraceWin - CEA/DSM/DAPNIA/SACM



Cavity OFF

$$\sigma_{y \text{ OFF}} = 0.04 \text{ mm}$$

Ele: 11 [2.6475 m] NGOOD : 30000 / 30000 TraceWin - CEA/DSM/DAPNIA/SACM



Cavity ON

$$\sigma_{y \text{ ON}} = 0.20 \text{ mm}$$

- Vertical deflection at zero crossing
- Input power 7 MW \rightarrow $U=1.55$ MV/m
- Beam energy $E=177$ MeV
- Bunch Length $\sigma_z=0.225$ mm (rms)
- $R_{12} = 1.6$ m (from cavity to screen)

$$\sigma_{BL} = \sqrt{\sigma_{ON}^2 - \sigma_{OFF}^2} = 0.197 \text{ mm}$$

$$\sigma_{BL} = R_{12} \cdot \frac{U}{E} 2\pi \frac{\sigma_z}{\lambda} \rightarrow \sigma_z = 0.223 \text{ mm}$$


RF deflector
powered by a klystron of DB Linac




Energy spread measurement

Ele: 13 [3.4143 m] NGOOD : 10000 / 10000 TraceWin - CEA/DSM/DAPNIA/SACM

Ele: 13 [3.4093 m] NGOOD : 40000 / 40000 TraceWin - CEA/DSM/DAPNIA/SACM




β - emittance



with energy spread $\sigma_E/E = 1\%$


- assuming spectrometer $\alpha \approx 30^\circ$, $\rho \approx 1$ m
- synchrotron light on the OTR \Rightarrow C-foil shielding (as proved on CT line)
- Time resolution with bandwidth > 250 MHz requires new ADC cards



Beam Position Monitor

Specifications : single bunch & multi-bunch operation (1-64 @ 3 GHz) 0.5 nC

- reentrant cavity original design from *R. Bossard (CERN)*
- proposed and developed for TTF (*M. Luong, C. Simon - DAPNIA*)




new design for CALIFES:

- higher dipole frequency with larger frequency separation between monopole and dipole modes
- low exposition of coupling loops to electric fields


mode	F (GHz)	Q	R/Q
monopole	3.85	24	22.3 (on axis)
dipole	5.94	43	1.1 (at 2 mm)

dipole mode : will be tuned to 5.996 GHz for resonant operation with 64 bunches





Mechanical model



Electronics

- 180° hybrid coupler
- direct detection for sum signal
- synchronous detection for delta signal

Summary

- good linearity and resolution $\sim 10 \mu\text{m}$
- should not be expensive (standard electronics)



2005 : definition of the probe beam linac

⇒ to freeze the architecture before Christmas !!!

2006 : specifications setting up, fabrication of components


additional human resources expected beginning of 2006

2007 : installation in CLEX building assumed ready end of 2006

2008 : start of commissioning



THERE **IZNOGOU**D PROBE BEAM ... WITHOUT **CALIFES** !!!



Time schedule

