# CTF3 Laser Status

Massimo Petrarca 3<sup>rd</sup> year PhD student in physics Univ. "La Sapienza" Rome

CLIC March 30 2007

## *GENERAL* LASER CHAIN LAYOUT



## General pulse structure layout

not in scale





DL5

~3 kW

2 μJ/pulse

1.5 GHz Nd:YLF Oscillator+ preamplifier



Spontaneous emission from AMP1 rod. Cylindrical lenses are present to focus the pump diode into the rod

Improvements on the beam spot quality



I = 70A

I=90A P=13.2W I=90A P=12.9W

DL1

DL3

DL2

200 µs, 5-50 Hz

3 pass Nd:YLF

amplifier

х5

diode pump 25 kW peak

1.5 GHz Nd:YLF Oscillator+ preamplifier 400 µs, 5-50 Hz 3-pass Nd:YLF amplifier x300 diode pump 15 kW peak

Project specification: ~3 kW ; 2 μJ/pulse 200 µs, 5-50 Hz 3 pass Nd:YLF amplifier x5 diode pump 25 kW peak

Peak Power

150

300

Time [us]

450

Time structure of the macro pulse coming out of AMP1 Peak Power, Gain and Energy Measured @ 90A

The peak power of the macro pulse thus the the gain and micro pulse energy are well above the specs



600

525

450

375

300

225

150

75 0

Gain

Gain



 $6.8 \cdot 10^{-7}$ 

3.4 . 10 - 7



200 µs, 5 Hz

3 pass Nd:YLF

diode pump 25 kW peak

amplifier

In order to obtain more free space on the optical table the second amp. has been disassembled and assembled again. Now the other devices can be mounted on the table.

Spontaneous emission from AMP2 rod. Cylindrical lenses are not present

400 μs, 5 Hz

3-pass Nd:YLF

amplifier

x300

diode pump 15 kW peak

1.5 GHz

Nd:YLF

Oscillator+

preamplifier

After straightforward alignment: Beam spot after AMP1 and AMP2 both @ 90A



With lens to fit the camera Without lens

1.5 GHz Nd:YLF Oscillator+ preamplifier



#### Project specification: ~15 kW ; 10 μJ/pulse

After straightforward alignment: Time structure Gain, Peak Power and Energy when AMP1 and AMP2 are both @ 90A

Rod R=5mm

Outgoing Beam R=5mm

Incoming Beam R=8mm



600



The micro pulse specified in the project is still not achieved Why? 
Losses due to beam cut into AMP2

# Gain & Beam cut losses



## **Reducing Telescope**

In order to decrease the beam spot dimension thus the beam cut losses through AMP2, a decreasing telescope has been installed between the two amplifier. The beam size without telescope is too big for 2 reasons: 1) a non collimating telescope before AMP1 is present 2) The Nd:YLF acts like a diverging lens



Power measurements to control the beam cut losses : AMP2 is off, the amplified beam from AMP1 @ 90A is sent into AMP2 AMP2 is off, the unamplified beam from AMP1 @ 0A is sent into AMP2

## Beam Spot vs AMP1 diodes current

Beam spot Before AMP2



The symmetry in intensity is satisfactory

But the shape is elliptical → thermal effect during amplification: Nd:YLF acts like diverging lens→ cylindrical lenses to compensate for have to be put.

#### **"POCKELS CELL " POSITION**



## POCKELS CELL (PC) INSTALLATION



## POCKELS CELL (PC) INSTALLATION TRANSMISSION EFFICIENCY



## **Fluctuations**





*With iris, to slightly cut the beam the noise is reduced* 

The reason of this fluctuation (noise) has to be investigated:
1) Spot size dimension → reflection (maybe into the rod) .... ?!
2) Spontaneous emission → noise ... ?!

## WHAT IS REMAINING ?



#### Future work:

1) Need to control the AMP2 performance (peak power, beam spot profile, saturation) when the new driver will work.

2) Need to install the beam deflector in order to remove the background signal that is not going to be used  $\rightarrow$  less energy density through the optics, less undesired effects.

3) Need to study and look into the intensity instability problem: preamp. beam size problem into the rod? pre lasing noise into AMP1 and AMP2? ...??

4) Need to instan the harmonic generation crystals, check their efficiency, the beam spot profile after them and final UV micro pulse energy.

5) Need to install the phase coding, actually under study from S. Cialdi and I. Boscolo @ University of Milan – INFN.

## The End