




Fabrication of photo-injectors for CTF3 and for the NEPAL test stand



Raphaël Roux

1. Status of the construction of the photo-injector for the drive beam linac
Funded by CARE
2. Status of the construction of the NEPAL beamline
Funded by CARE
3. Project of the photo-injector for the probe beam linac

1. Status of the construction of the CTF3 photo-injector

- **Modification of the technical drawings of the gun upon a CERN request** due to the insertion of photo-cathode transfer chamber (August)

⇒ All the cooling channels in the gun had to be re-designed

⇒ Makes difficult to support the gun

- **Finalization of the technical drawings of the NEG envelop around the gun**

Strong collaboration with CERN is mandatory since the NEG coating is done there



⇒ drawings are finished

1. Status of the construction of the CTF3 photo-injector

- **Modification of the magnetic design: 2 coils instead of 3**

No enough space for pumping with 3 coils

Solenoids ordered in June, one was modified in September taking into account the data of the CERN cooling system



With a gaussian laser

=>delivery of solenoids in December

1. Status of the construction of the CTF3 photo-injector

Construction of a prototype to valid HF simulations

Ordered in March last piece received in November, 4th !!


History:

- ordered in March to the French company DURUAL
- test cavity received in April not satisfying
- several tries later, order in beginning of June, foreseen delay: 2 months
- the firm begins (we suspect) the work only in October

Set up of the HF measurement apparatus begun the 10th


Duration: 2 months but we hope to order the final gun before the end of the year

1. Status of the construction of the CTF3 photo-injector



Coupling aperture

1. Status of the construction of the CTF3 photo-injector




First half cavity with the hole for the photo-cathode

Central cavity

Last cavity with coupling holes

Cooling channels


1. Status of the construction of the CTF3 photo-injector



Ducts for NEG pumping



2. Status of the construction of the NEPAL beamline



- RF gun will be built almost in same time with the one for CTF3
- photo-cathode preparation chamber under construction in our workshop
- laser from HighQ should be delivered next month as all the optical stuff
- drawings of magnetic elements are available
- modulator is under construction

But :

New shielding to radiations is mandatory due to more severe legal threshold

=>first study implied a **cost too high**

=>**second study under way** reducing the area of the NEPAL room

civil engineering is foreseen

3. Project of a photo-injector for the probe beam linac


Probe
Beam linac



Probe Beam
Photo-Injector
(PBPI):




Energy	200 MeV
Normalised r.m.s. emittance	20π mm mrad
Energy spread	$\pm 2\%$
bunch charge	0.5 nC
Number of bunches	Variable from 1 - 64
Bunch spacing	0.333 ns
r.m.s. bunchlength	0.75 ps



SACLAY
SACM




Energy	$\sim 4 - 5$ MeV
Normalised r.m.s. emittance	20π mm mrad <
Energy spread	$\pm 2\%$ <
bunch charge	> 0.5 nC



3. Project of a photo-injector for the probe beam linac

Initial PBPI design derives from PHIN photo-injector :




Modifications (because spec. are \neq) :


- smaller Iris aperture (15 mm instead of 20 mm for PHIN).
- Cathode wall angle set to zero.
- Iris profile is circular and connexe walls are obliques.
- « upper part » of each cellule profile is rectangular. (easier to re-machine).

HF Simulations performed by Julien Brossard



3. Project of a photo-injector for the probe beam linac



HFSS simulations



$$Q = 14400, R_s = 7.84 \text{ M}\Omega \Rightarrow P_{\text{HF}} = 5.2 \text{ MW} \text{ for } 80 \text{ MV/m}$$



NEG coating

E (MeV)	5.35
σ_r (mm)	2.33
FWHM _z (ps)	8
$\sigma_{\gamma/\gamma}$ rms (%)	0.33
ε (π mmrad)	6.5

CONCLUSION

► Photo-injector for the drive beam linac

measurements and re-machining of prototype under way
do our best to catch up for a delivery before summer but no guaranty

► Construction of the NEPAL beamline

Most of components will be available before the end of next year
but incertitude on the delay to get the authorization

► Photo-injector for the probe beam linac

HF design of the gun and coil calculations are completed
detailed technical drawings under way
design simpler => less problems