



Questions and Answers

L. Rinolfi




CLEX layout



Goal: Clarify as much as possible with all Institutes / Collaborations the questions which are still open

The information below are based on the input known today and should be updated



Overview



Magnets

Power supplies

Beam diagnostic

Radiation monitoring system

Vacuum

Klystron


Alignment

Civil engineering

Cooling and ventilation

Controls

Planning



Magnets



Contact person: Thomas Zickler


CERN provides:

- ✓ Dipoles for spectrometer lines
- ✓ Solenoids around LIL sections (2 x 17)
- ✓ Correcting coils around LIL sections

All other magnets provided by the Collaborations



Dipole Type BHB
(or MDX)



Power supplies




Contact person: Roger Genand

Power supplies for the Test Stand 30 GHz paid by Uppsala Collaboration

All power supplies provided by CERN with standard control

=> Collaborations should provide the requested characteristics



Beam diagnostic (BPM's)



Contact person: Lars Soby

CERN BPM = Beam Position Monitor (Φ 40 mm)

INFN BPM = Beam Position Monitor (section 90 x 40 mm)


CEA BPM = Beam Position Monitor (Φ 40 mm)

CERN WCM


NWU BPR = Beam Position Monitor (for bunch length behavior)




CLEX meeting CERN
12th July 2006



INFN




CEA



Spain




NWU




Beam diagnostic (MTV)

Contact person: T. Lefèvre

MTV = Ensemble camera & mirrors from scintillator screen or from synchrotron light



Synchrotron light output from a dipole



Radiation monitoring system



Contact person: Markus Rettig

Existing System

ARCON (developed for LEP)

6 monitors for stray radiation survey

3 monitors for induced activity

→ not possible to extent to future needs.




Future system for CTF3 operation with CR and CLEX:

RAMSES (developed for LHC and CNGS)

8 additional detectors for stray radiation survey

11 additional detectors for induced activity monitoring




Vacuum



Contact persons: Jan Hansen, Jean-Pierre Bertuzzi


CERN Standard should be applied by Collaborations

- The vacuum chamber components are in Stainless Steel or Aluminum alloy (The latter is best suited for radiation issues and minimize the resistive wall effects).



Vacuum chambers, pumping ports and bellows by LNF / INFN for the Delay Loop

- For TL2 => India collaboration (Extruded pipes)
- Vacuum control (HV, gauges,...) according to CERN standard






Klystron, modulator and RF



Contact persons: Gerry McMonagle, Ghislain Rossat, Jean Mourier

- CERN provides 1 klystron 43 MW and waves guides network
- CEA/DAPNIA provides 1 modulator and RF components
- CERN provides components of the low level RF





Alignment



Contact persons: Tobias Dobers, Frank Tecker


- MAD-X used for the geometrical data
 - Alignment made by Survey group (TS/SU) within ± 0.1 mm
- => Information about targets and jigs should be provided by Collaborations**



Alignment of a CERN BPM





Type Q*D
(or QL3)



CLEX Civil engineering




Contact person: Michael Poehler



D 6x1: Doors with access control

D 6xx: Safety issues

D 6xx: Doors closed with concrete blocks



Cooling and Ventilation



Contact person: Yannic Body

Demineralized water $P = 13$ bars (for magnets, etc...), $T = 25$ °C

Thermalized water $T = 30$ °C (for RF components) $P = 5$ bars

Compressed air $P = 8 - 10$ bars


Air conditioning installed later on



600 kW in CLEX

CLEX meeting

12th July 2006




Controls



Contact person: Stephane Deghaye

- FEC Hardware
 - VME: powerPC/LynxOS
 - cPCI: x86/Linux
 - PLC: Siemens
- FEC Software
 - FESA: C++ framework
- High Level Software
 - Java (Swing for GUI) + CMW (CORBA) for com. with FEC
- Control Generic Applications
 - Basic Control: Working Sets + Knobs
 - Analogue Signals: XsamGen + OASIS
 - Alarms: LASER



Planning summary



CLEX: building ready: end 2006
ready to install equipment: **Mid June 2007**
Klystron gallery: building ready: March 2007
ready to install equipment: **Mid June 2007**


TL2: Install 2. half 2007
TL2*: Install end 2007

Beam in CLEX : from March 2008 onwards

Two-Beam test stand : First beam as early as possible: April 2008

Probe Beam Laser In "old" laser room above CTF2: from mid 2006
 In CTF3 earliest beginning 2008
 Califes installation half year 2007
 Commissioning in parallel with TBTS and PETS tests (2008)

TBL : goal first tests in March 2008



Conclusion



If some questions remains unclear

Please ask for clarification